

Alleston Solar Farm, Pembrokeshire

Sustainable Drainage Maintenance Plan

Reference Number: 3.0.9

October 2024





Alleston Solar Farm
333100437
October 2024
A Harman
Detailed SuDS Asset Operation and Maintenance Plan

1. Executive Summary

- 1.1. This Detailed Sustainable Drainage System (SuDS) Asset Operation and Maintenance Plan has been prepared by Stantec, on behalf of our client, Alleston Clean Energy Limited, to outline the necessary SuDS maintenance activities to be carried out on all proposed SuDS features.
- 1.2. This Maintenance Plan has been prepared in support of development proposals for Land at Alleston Farm, Lower Lamphey Road, Lamphey, Pembrokeshire. This Maintenance and Operation Plan has been prepared in line with national policy and industry guidance. Continued SuDS maintenance will ensure the effective operation of the Surface Water Drainage Strategy, including the continued SuDS performance for water quantity, water quality, amenity, and biodiversity.
- 1.3. For further information, refer to the Stantec Alleston Solar Farm, Flood Consequences Assessment.

2. Responsibilities

- 2.1. Construction Design Management (CDM) regulations, 2015, dictate, designers must identify, mitigate, and reduce the likelihood of maintenance risks where possible.
- 2.2. During the construction phase, the principal contractor is responsible for ensuring the SuDS maintenance activities as specified in this document are carried out. The principal contractor should adhere to strict preventative measures to ensure pollution of SuDS and onsite watercourses is avoided. The principal contractor is also responsible for the preparation of a Construction Phase Health and Safety Plan, to ensure the risks associated with the construction of SuDS features have been identified, mitigated against, and controlled.
- 2.3. Through consultation with Pembrokeshire SuDS Approval Body (SAB), the SAB have indicated they will not adopt any of the proposed SuDS features at this development. Following construction, the maintenance and operation of the proposed SuDS features will therefore be passed onto the landowner. The landowner will likely appoint a private SuDS Maintenance Company to undertake the required SuDS maintenance activities during the operational phase of the development.

3. SuDS Operation and Maintenance Policy

- 3.1. This drainage strategy has been designed to establish a SuDS management train to satisfy the statutory SuDS Standards S1 to S6 as set out under the SuDS Standard document (Statutory standards for sustainable drainage systems designing, constructing, operating and maintaining surface water drainage systems, Welsh Government, 2018). The SuDS Standards are the minimum criteria a SAB require for approvals. These standards aim to manage rainwater sustainably, contrasting with traditional underground pipe-based drainage systems. In summary, the six standards:
 - Surface Water Runoff Destination (S1): Prioritise the choice of runoff destination.
 - Surface Water Runoff Hydraulic Control (S2): Control the volume and rate of runoff.
 - Water Quality (S3): Provide treatment for runoff to prevent negative downstream impact.

^{\\}Bri-vfps-001\bri\Projects\333100437 Alleston Solar Farm\Hydro\Reports\SuDS Maintenance Plan\241002_333100437300_TN001_SuDSMaintenancePlan_AllestonSolar Rev C.docx



- Amenity (S4): Enhance the environment and create pleasant spaces.
- Biodiversity (S5): Promote biodiversity and habitat creation.
- Design of Drainage (S6): Ensure proper construction, operation, and maintenance, including structural integrity.
- 3.2. Standard S6 'Design of Drainage for Construction, Operation and Maintenance and Structural Integrity', explains 'all elements of the surface water drainage system should be designed to ensure maintenance and operation can be undertaken (by the relevant responsible body) easily, safely, cost-effectively, in a timely manner, and with the aim of minimising the use of scarce resources and embedded carbon (energy).'
- 3.3. Standard S6 sets out the required information expected in the preparation of a Maintenance Plan, as included below;
 - 'Inspection and maintenance required for the system to function as designed with regard to meeting the performance levels set by compliance with these Standards.
 - Inspection and maintenance required during the establishment of vegetative components and for the long-term management of that vegetation.
 - Locations where sediment removal is necessary to ensure sediment control measures continue to function as designed, together with the anticipated frequency and appropriate means of sediment removal and disposal'.
- 3.4. S6 advises guidance on the production of a Maintenance Plan can be found in the *CIRIA SuDS Manual C753*, 2015. The information to be included in a Maintenance Plan, as indicated by the CIRIA guidance, and refined to ensure suitability to this development are listed below;
 - Location of all SuDS components on the site.
 - Summary of the design intent, how SuDS components work, their purpose and potential performance risks.
 - Depth of silt that will trigger requirement for removal.
 - Visual indicator that will trigger maintenance.
 - Maintenance requirements.
 - Maintenance plan.
 - Explanation of the objectives or the maintenance proposed and potential implications of not meeting those objectives.
 - Identification of areas where certain activities are prohibited.
 - An action plan for dealing with accidental spillages of pollutants.
 - Advice on what to do if alterations are to be made to a development or if service companies need to undertake excavations or other similar works that could affect the SuDS.
 - Details of whom to contact if pollution is seen in the system or if it is not working correctly.

^{\\}Bri-vfps-001\bri\Projects\333100437 Alleston Solar Farm\Hydro\Reports\SuDS Maintenance Plan\241002 333100437300 TN001 SuDSMaintenancePlan AllestonSolar Rev C.docx



- 3.5. In addition to the above, this technical note demonstrates the following;
 - The SuDS design should allow free, safe, and easy access (including easements where required) for all personnel, vehicles and machinery required to undertake maintenance of the SuDS (see Appendix A).
 - The SuDS design should ensure that all components which are intended to promote infiltration should incorporate or be preceded by a pretreatment component which effectively protects the infiltration surface from clogging (see Section 6).

4. Construction

- 4.1. Swale excavations should ideally be undertaken in dry weather, to prevent mobilisation of sediments from exposed surfaces. Native grass planting should be undertaken soon after excavation, to promote swale base and side-slope stabilisation. Signage should be erected to mark the position of swales, to prevent accidental damage during construction. Swales should be protected by silt fencing during the construction phase.
- 4.2. Excavation of infiltration trenches should be free of earth and rainwater to avoid contamination. Once constructed, silt fences should be installed around infiltration trenches during the construction phase.



5. Operation

Easy and Safe Access for Maintenance

- 5.1. In accordance with Statutory Standards for Sustainable Drainage Systems Designing, Constructing, Operating and Maintaining Surface Water Drainage Systems Standard S1, for correct operation of SuDS assets, adequate access must be provided for maintenance (see Appendix A). Whilst swale locations are indicative at this stage, swales are proposed entirely on the downslope side of proposed solar PV panel parcels, and not surrounded by development. Swales are also proposed to lie at least 5m from any onsite watercourse. Therefore, swales will be easily and safely accessible for maintenance activities.
- 5.2. In accordance with S6, infiltration trenches are located on the downslope side of proposed transformer stations, adjacent to maintenance access tracks and not within 5m of onsite watercourses. Therefore, infiltration trenches will also be easily and safely accessible for maintenance activities.

Operational Risk

- 5.3. In accordance with S1, the surface water drainage strategy has been designed to ensure no pumping is required, as such minimising the risk of operational failure and ensuring no operational energy use.
- 5.4. In accordance with S1, the health and safety risks associated with the operation of proposed Assets has been considered. All runoff generated onsite is discharged via infiltration trench at source. Hence, there is no permanent storage of water at surface, reducing the operational risk of the surface water drainage strategy. The proposed swales are designed with shallow 1 in 4 side slopes and a depth of only 150mm. 150mm deep swales may have vertical side slopes, in accordance with CIRIA guidance, thus the proposed swales adopt a safe design.

Sediment Disposal

- 5.5. If contaminated, the waste needs to be removed and safely disposed of as contaminated waste in a legal manner with appropriate waste classification testing where required.
- 5.6. If uncontaminated, the sediment should be utilised onsite, returned ideally to the location of the upstream point of origin as fill if suitable, together with suitable binding or scour prevention works, or spread out evenly onsite in suitable locations ensuring flow routes are not disturbed. The upstream sediment swales catchment of this Alleston site is not considered to contain land uses posing a significant pollution risk, and therefore the sediment could be considered uncontaminated.

Cost-effective Operation and Maintenance

5.7. In accordance with S6, the cost effectiveness of operation has been considered. The development has been designed with permeable surfaces where possible, to ensure a very minimal increase in impermeable area. This significantly reduces the required provision of SuDS. Surface water runoff generated by proposed impermeable development will be managed at source, therefore reducing the required scale of SuDS assets. Pumping is not proposed, thus ensuring no operational energy use. As such, the affordability of the proposed Surface Water Drainage Strategy has been maximised.



Accidental Spillages and Pollution Prevention

- 5.8. During the construction phase, it is the responsibility of the principal contractor to mitigate against spillages. During the operational phase, this responsibility will be transferred to the private SuDS maintenance company. Both are responsible for ensuring spillage kits are available, in the event of a spillage.
- 5.9. In the event of a spillage, Natural Resources Wales (NRW) should be contacted, either online through the 'Report an Incident' ¹webpage, or via calling 0300 065 3000.
- 5.10. An Environmental Pollution Protection Plan should also be prepared and made available to those working onsite. The SuDS Manual explains the two major pollution sources from construction activities are sediment pollution and oil and hydrocarbon spills. Mitigation activities to avoid accidental pollution are included below (see Table 5-1 and Table 5-2).

Activity	Pollution Prevention Methods Required
Excavated ground and exposed ground	Silt fences, hay bales or stilling ponds should be placed downstream of excavated or exposed ground. Runoff diversion or interception devices should be placed upstream.
Stockpiles	Stockpiles should be located away from onsite watercourse and SuDS features. Protective coverings should be applied on stockpiles.
Plant and wheel washing	This activity should take place in designated locations. The area should be tanked and not be allowed to discharge to watercourse or ground. Proprietary treatment can be employed to collect solid waste materials. This waste will be treated as contaminated waste.

Table 5-1: Measures to Prevent Sediment Pollution (CIRIA C753)

Table 5-2: Measures to Prevent Oil and Hydrocarbon	n Pollution (CIRIA C753)
--	--------------------------

Activity	Pollution Prevention Methods Required
Use of machinery	Appropriate maintenance of machinery and checking for oil leaks
Storage	Corectly storing fuel, checking for wear and tear on tanks, regular emptying of bunds and tanks secured to prevent vandalism
Refuelling	Drip tray use, procedures for refuelling, designated areas for refuelling, emergency spill kit located near refuelling areas

Protocol in the Event of Spillage

- 5.11. In the event of a hydrocarbon/oil spill, booms should be employed to capture the oil/hydrocarbon films, allowing for subsequent removal.
- 5.12. In the event of pollution in the system, or if the system is not working correctly, the private SuDS maintenance company should be contacted.

Future Alterations and Utilities Considerations

5.13. If alterations are to be made to the development or if service companies need to undertake excavations or other similar works that could affect SuDS assets, permission should first be sort from the landowner in consultation with the private SuDS maintenance company for a suitable strategy to be developed to ensure continued SuDS performance.

¹ Natural Resources Wales / Report an incident

^{\\}Bri-vfps-001\bri\Projects\333100437 Alleston Solar Farm\Hydro\Reports\SuDS Maintenance Plan\241002_333100437300_TN001_SuDSMaintenancePlan_AllestonSolar Rev C.docx



6. Maintenance Requirements

- 6.1. The proposed maintenance activities included below (see Table 6-1, Table 6-2 and Table 6-3) have been taken from the CIRIA guidance.
- 6.2. The CIRIA guidance breaks down maintenance activities into maintenance schedule classification groups. Regular maintenance activities consist of basic tasks carried out on a frequent schedule. Occasional maintenance activities are required periodically and are less frequent and less predictably scheduled than regular maintenance. Remedial activities are associated with intermittent tasks that may only be required to rectify faults with SuDS Assets. These activities are thus not scheduled activities.
- 6.3. The frequency of the various maintenance activities should be refined as necessary, based on site specific requirements.

Sediment Collection Swale

Design Intent, Purpose, and Potential Performance Risks

6.4. Sediment collection swales are proposed to intercept all runoff from proposed parcels of solar PV panels, and convey surface water to onsite watercourses, following the fall of the land. Some infiltration would be expected along the base and side-slopes of swales, whilst temporary storage is provided on the upstream side of leaky dams. Thus, the implications of improper maintenance would result in the conveyance of sediment pollution to onsite watercourses and the increase in frequency of exceedance events and subsequent erosion of hillside slopes, thus again increasing sediment pollution.

Visual Indicators Prompting Maintenance Activities

6.5. Visual indicators triggering the requirement for maintenance include the presence of debris, excessive grass lengths, sediment accumulation, areas of bare earth, damage to check dams and an increase in the frequency of swale bank overtopping.

Sediment Accumulation Depths

6.6. Removal of sediment within swales are undertaken when the sediment depth reaches a level that restricts and so impairs the operation of the asset. In line with CIRIA guidance, the typical frequency of sediment removal should ensure sediment deposits do not exceed 25mm. However, given proposed swales are primarily for sediment collection, rather than conveyance of surface water, sediment accumulation up to 75mm, is appropriate, after which removal is required.

Maintenance Activities

6.7. The primary role of swales at this development, is for the collection of sediment in runoff generated in solar PV panel parcels. Thus, the frequency of sediment removal required at this site, may be higher than other sites.



Maintenance Schedule	Required Action	Typical Frequency		
Regular	Remove litter and debris	Monthly, or as required		
maintenance	Cut grass – to retain grass height within specified design range*	Monthly (during growing season), or as required in the Outline Landscape and Ecological Management Plan (oLEMP)		
	Manage other vegetation and remove nuisance plants	Monthly at start, then as required		
	Inspect inlets, outlets, and overflows for blockages, and clear if required	Monthly		
	Inspect infiltration surfaces for ponding, compaction, silt accumulation, record areas where water is ponding for >48 hours	Monthly or when required		
	Inspect vegetation coverage	Monthly for 6 months, quarterly for 2 years, then half yearly		
	Inspect inlets and facility surface for silt accumulation, establish appropriate silt removal frequencies	Half yearly		
Occasional maintenance	Reseed areas of poor vegetation growth, alter plant types to better suit conditions, if required	As required or if bare soil is exposed over 10% or more of the swale treatment area		
Remedial actions	Repair erosion or other damage by re-turfing or reseeding	As required*		
	Relevel uneven surfaces and reinstate design levels	As required		
	Scarify and spike topsoil layer to improve infiltration performance, break up silt deposits and prevent compaction of the soil surface	As required		
	Remove build-up of sediment on upstream gravel trench, flow spreader or at top of filter strip	As required		
	Remove and dispose of oils or petrol residues using safe standard practices.	As required		
*Whilst CIRIA guidance recommends mowing should retain grass lengths of 75-150mm across treatment surfaces, longer vegetation lengths are not considered to pose a significant risk to functionality and as such, grass lengths suitable for native grass planting can be adopted.				
** Leaky dams constructed with permeable material (e.g. rip-rap or timber boards) are proposed every 10-20m to slow the velocity of surface water within the sediment collection swales to mitigate against scour and resultant re-suspension of collected sediments.				

Table 6-1: Vegetated Swale Maintenance Activities (CIRIA C753)

6.8. Leaky dams should be repaired as required.

^{\\}Bri-vfps-001\bri\Projects\333100437 Alleston Solar Farm\Hydro\Reports\SuDS Maintenance Plan\241002_333100437300_TN001_SuDSMaintenancePlan_AllestonSolar Rev C.docx



- 6.9. A biodegradable erosion protection mat is proposed along the length of exceedance flow routes generated when swales overtop in high intensity rainfall events. The inspection and maintenance required during the establishment of vegetation in these areas will fall under the Landscape Management Plan.
- 6.10. Any damage due to sediment removal or erosion should be repaired and immediately reseeded or planted.

Infiltration Trenches

Design Intent, Purpose, and Potential Performance Risks

- 6.11. Infiltration trenches are proposed on the downslope side of transformer stations (the only proposed impermeable development). Infiltration trenches are protected from sediment accumulation by filter strips of minimum width 3m (see below filter strip maintenance) located between transformer stations and the trenches themselves. Runoff generated by transformer stations will flow overland across minimum 3m wide filter strips prior to interception by infiltration trenches. Infiltration trenches will discharge this surface water to ground.
- 6.12. Thus, the implications of improper maintenance include the increase in runoff generated by the site.

Visual Indicators Prompting Maintenance Activities

6.13. Visual indicators triggering the requirement for maintenance include the presence of debris, vegetation growing over the infiltration trench surface, sediment accumulation and continuous high water levels within the infiltration trench.

Maintenance Activities

Maintenance Schedule	Required Action	Typical Frequency
Regular Maintenance	Remove litter, debris, and trash	Monthly
Maintenance	Cleaning of any gutters and any filters on downpipes	Annually (or as required based on inspections)
	Trimming any roots that may be causing blockages	Annually (or as required)
	Inspect for and remove sediment and debris from floor of inspection tube	Annually (or as required)
	Cut grass – around trench	Half yearly: spring (before nesting season) or as required
Remedial actions	Replace or clean void fill if performance deteriorates or failure occurs	As required
	Replacement of clogged geotextile	As required
Monitoring	Check infiltration trench inspection tube to ensure emptying is occurring	Annually

\\Bri-vfps-001\bri\Projects\333100437 Alleston Solar Farm\Hydro\Reports\SuDS Maintenance Plan\241002_333100437300_TN001_SuDSMaintenancePlan_AllestonSolar Rev C.docx



Maintenance Schedule	Required Action	Typical Frequency
Regular	Remove litter, debris, and trash	Monthly (or as required)
Maintenance	Cut the grass – to retain grass heights within specified design range	Monthly (during growing season), or as required in the Outline Landscape and Ecological Management Plan (oLEMP)
	Manage other vegetation and remove nuisance plants	Monthly (at start, then as required)
	Inspect filter strip surface to identify evidence of erosion, poor vegetation growth, compaction, ponding, sedimentation, and contamination (e.g. oils)	Monthly (at start, then half yearly)
	Check flow spreader and filter strip surface for even gradients	Monthly (at start, then half yearly)
	Inspect gravel flow spreader upstream of filter strip for clogging	Monthly (at start, then half yearly)
	Inspect silt accumulation rates and establish appropriate removal frequencies	Monthly (at start, then half yearly)
Occasional maintenance	Reseed areas of poor vegetation growth, alter plant types to better suit conditions, if required	As required or if bare soil is exposed >10% of the filter strip area
Remedial actions	Repair erosion or other damage by re-turfing or reseeding	As required
	Relevel uneven surfaces and reinstate design levels	As required
	Scarify and spike topsoil layer to improve infiltration performance, break up silt deposits and prevent compaction of the soil surface	As required
	Remove build-up of sediment on upstream gravel trench, flow spreader or at top of filter strip	As required
	Remove and dispose of oils or petrol residues using safe standard practices	As required

Table 6-3 Filter Strip Maintenance Activities (C753)



7. Caveats

- 7.1. The conclusions made in this SuDS Asset Operation and Maintenance Plan are based on data available at the time of the study and on the subsequent assessment that has been undertaken in relation to the development proposals as outlined in the associated Flood Consequences Assessment (FCA) report.
- 7.2. The Construction (Design and Management) Regulations (CDM Regulations) will apply to any future development of this site which involves "construction" work, as defined by the CDM Regulations. As such it is the responsibility of the proposed developer (ultimate client) to fulfil its duties under the CDM Regulations.

DOCUMENT	ISSUE	RECORD
	ICCOL	ILCOILD


Report	Rev	Date	Prepared	Checked	Reviewed (Discipline Lead)	Approved (Project Manager)
333100437/300/TN001	A	08/07/24	A Harman	A Johns	P Mennell	P Mennell
333100437/300/TN001	В	13/09/24	A Harman	L Whalley	P Mennell	P Mennell
333100437/300/TN001	С	02/10/24	A Harman	L Whalley	P Mennell	P Mennell


This report has been prepared by Stantec UK Limited ('Stantec') on behalf of its client to whom this report is addressed ('Client') in connection with the project described in this report and takes into account the Client's particular instructions and requirements. This report was prepared in accordance with the professional services appointment under which Stantec was appointed by its Client. This report is not intended for and should not be relied on by any third party (i.e. parties other than the Client). Stantec accepts no duty or responsibility (including in negligence) to any party other than the Client and disclaims all liability of any nature whatsoever to any such party in respect of this report.

T: +44 1173 327 840 E: bristolqueensquare@stantec.com



Appendix A Proposed SuDS Maintenance Drawing





Q

Statkraft

S2 - FOR INFORMATION

This document is suitable only for the purpose noted above. Use of this document for any other purpose is not permitted.

Client/Project STRATKRAFT UK

Client/Project Logo

& SWALE REVISED.

P03 UPDATED MASTERPLAN

P02 UPDATED MASTERPLAN

Issued/Revision

Issue Status

P01 FIRST ISSUE FOR PLANNING

ALLESTON SOLAR FARM,

PEMBROKESHIRE

Title

PROPOSED SUDS MAINTENANCE

100	150	200	2501
SCALE	1:2500		

Project No. 333100437 A1 Scale 1:2500

CR PM 2024.10.04

By Appd YYYY.MM.DD

CR AH PM 2024.07.08 Dwn. Dsgn. Chkd. YYYY.MM.DD

CR

CR AH

PM2024.09.12PM2024.07.24AJ2024.07.08

Revision P04

Drawing No. 333100437-STN-HDG-XX-DR-HY-4102